



February 9, 2026
Sent Via: E-mail

**ADDENDUM # 1
TO PLANS AND SPECIFICATIONS FOR:**

2026 PCC Patch Project

To all plan holders:

The plans and specifications for the above referenced project shall be changed as follows:

- CD Joints are required for transverse joints in patches greater than 15' long. See SUDAS Figure 7040.102 replacing C joints with CD.
- PCC mix shall be C-4 with no substitute cementitious materials (straight cement).

THIS ADDENDUM #1 SHALL BE ACKNOWLEDGED WITH THE BIDDER'S PROPOSAL.

A handwritten signature in blue ink that reads 'Austin Morrow'.

Austin Morrow, PE
City Engineer